

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 30 1970
CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Fell & Wolfe Oil Company

Complete Address Box 7447 Tulsa, Okla. 74105

Lease Name T. E. Mattson Well No. # 1

Location C S/2 SW SW Sec. 19 Twp. 20 Rge. 5 (E) (W)

County McPherson Total Depth 3331'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Art Lamb Casing Pulling

Address Hutchinson, Kansas License No. # 440

Operation Completed: Hour 3 PM Day 27 Month 6 Year 70

The above well was plugged as follows:

8 5/8"-110'-Circulated w/cement. 5 1/2"-3290'-Cemented. Sand hole to 3275'.

5" Sax. cement 3275' to 3225'. Mud 3225' to 140'. Bridge 140' to 130'.

30 Sax. cement 130' to 70'. Mud 70' to 40'. Bridge 40' to 30'.

10 Sax. cement 30' to 0. Pulled 2585'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging SupervisorDATE 6/30/70INV. NO. 2126-4