

KANSAS

Form CP-3

Rev. 6-26-62

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 18 1967CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Fell & Wolfe Oil Co.Complete Address Box 7447 Tulsa, Okla.Lease Name Swanson Well No. # 3Location C W/2 NE SW Sec. 18 Twp. 20 Rge. 5 (E) (W) County McPherson Total Depth 3349'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Art Lamb Casing Pulling Co.Address: Hutchinson, Kansas License No. 440Operation Completed: Hour 2 PM Day 14 Month 9 Year 67

The Above well was plugged as follows:

8 5/8"-159'-Circulated w/cement. 5 1/2"-3330'. Cemented. Sand hole to 3300'.5 Sax.cement 3300' to 3250'. Mud 3250' to 130'. Bridge 130' to 120'.25 Sax.cement 120' to 50'. Mud 50' to 40'. Bridge 40' to 30'.10 Sax.cement 30' to 0. Pulled 2620'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 9/18/67INV. NO. 6346-WSigned: Hughes

Well Plugging Supervisor