

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 -113-20,745.00.00 (of this well)

Operator's Full Name Culver-Grounds Oil Properties, Inc.

Complete Address 1432 Ranch Rd. McPherson, Kansas 67460

Lease Name Nelson "B" Well No. 1

Location NW SW SE Sec. 18 Twp. 20 Rge. 5 (EX) (W) X

County McPherson Total Depth 3390'

Abandoned Oil Well Gas Well Input Well SWD Well D&A (Lost hole)

Other well as hereafter indicated Lost hole, dropped tubing & stuck the packer.

Plugging Contractor Co. Tools & HOWCO

Address 1432 Ranch Rd. McPherson, Kansas License No. _____

Operation Completed: Hour 2:45 Day 11 Month 10 Year 1980
PM

The Above well was plugged as follows:

Squeezed thru 8 5/8" surface casing with 4 sx hulls,
15 sx cement, 15 sx mud-gel, 1 sx hulls, and 85 sx cement.
Max. pres. 500#. Shut in pres. 300#.
Recovered 1376' of 5 1/2" casing.
Packer stuck at 1800'.
3389' of 5 1/2" casing cemented with 75 sx cement.
175' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

Signed: Deane L. Rankin
Well Plugging Supervisor

INVOICED

DATE 10-28-80

INV. NO. 4041-W

RECEIVED
STATE CORPORATION COMMISSION

OCT 14 1980

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
245 North Water
WICHITA, KANSAS 67202

October 28, 1980

WELL PLUGGING AUTHORITY

Well No.	1
Lease	Nelson "B"
Description	NW SW SE
Section	18-20S-5W
County	McPherson
Total Depth	3390'
Plugging Contractor	Co. Tools & HOWCO


Culver-Grounds Oil Properties, Inc.
1432 Ranch Rd.
McPherson, Kansas 67460

Gentlemen:

This is your authority to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

This authority is void after ninety (90) days from the above date.

Yours very truly,


For Administrator

Mr. Duane L. Rankin, P.O. Box 967, Great Bend, Kansas 67530
is hereby assigned to supervise the plugging of the above named well.