

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Bradley BrothersComplete Address: 1009 Union Center. Wichita, Kansas 67202Lease Name Swanson Well No. # 1Location C S/2 SW SW Sec. 18 Twp. 20 Rge. 5 (E) // (W)County McPherson Total Depth 3346'Abandoned Oil Well X Gas Well Input Well SWD Well D & A Other well as hereafter indicated: Plugging Contractor: Braden-Deem, Inc.Address: Wichita, Kansas License No. # 580Operation Completed: Hour 11 AM Day 9 Month 8 Year 68

The Above well was plugged as follows:

10 3/4"-159'-Circulated w/cement. 5 1/2"-3283'-Cemented. Sand hole to 3275'.5 Sax.cement 3275' to 3225'. Mud 3225' to 160'. Bridge 160' to 150'.35 Sax.Cement 150' to 75'. Mud 75' to 40'. Bridge 40' to 30'.15 Sax.cement 30' to 0. Pulled 25 1/2"-5 1/2"-pipe.

RECEIVED

STATE CORPORATION COMMISSION

AUG 12 1968

CONSERVATION DIVISION

Wichita, Kansas

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8/12/68INV. NO. 8250-WSigned: [Signature]
Well Plugging Supervisor