

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Request Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

Rice

County. Sec. 21 Twp. 20 Rge. 10 (E) (W) XX

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines NE NE SW

Lease Owner Morgenstern & Specter

Lease Name Schurr "A" No. 4

Well No.

Office Address Russell, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 11-23-52

19

Application for plugging filed October 6, 1956

19

Application for plugging approved October 8, 1956

19

Plugging commenced October 10, 1956

19

Plugging completed October 15, 1956

19

Reason for abandonment of well or producing formation failure to produce profitably

If a producing well is abandoned, date of last production August 1956

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Arbuckle Depth to top 3304' Bottom 3307' Total Depth of Well 3307' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" O.D.	98'	2948.15' none
				5 1/2" O.D.	3307'	2948.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Sanded hole to 3260'. Dumped 6 sacks cement. Mudded hole to 150'.
Dumped 25 sacks cement & 10' rock bridge. Mudded and dumped 5 sacks
cement to top of cellar.

RECEIVED
STATE CORPORATION COMMISSION
OCT 25 1956
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Arnett Casing Pulling Co.

Address Hoisington, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Morgenstern & Specter

(employee of owner) or (owner or operator) of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Arthur Morgenstern
Barbara Russell
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of Oct, 1956

My commission expires

April 14-59

Notary Public.

PLUGGING

FILE SEC. 21 T. 20 R. 10W
BOOK PAGE 105 LINE 13

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15.159.04519.0000

Company- PABCO DRILLING CO., INC.
Farm- Schurr "A" No. 4

SEC. 21 T. 20 R. 10W
NE NE SW

Total Depth. 3307
Comm. 11-12-52 Comp. 11-23-52
Shot or Treated.
Contractor. Pickrell Drilling Co.
Issued. 2-7-53

County Rice
KANSAS



CASING:

8 5/8 98' w/ 75 sx cement
5 1/2 3307' w/ 50 sx cement

Elevation. 1766

Production. 25 bbls.

Meas. from top rotary bushing. Figures indicate Bottom of Formations.

red bed & shale	410
anhydrite	455
shale	1200
shale & lime shells	1400
lime & shale	1630
lime & shale breaks	1750
lime & shale	2110
shale & shells	2380
shale	2546
lime & shale	2690
lime	2855
shale & shells	2985
lime	3307
Total Depth	

SCOUT-TOPS:

Howard	2475
Severy sand	2544
Topeka	2570
Heebner	2846
Brown lime	2974
Lansing	2997
Conglomerate	3267
Simpson sand	3269
Second Simpson sand	3299
Arbuckle	3304

RECEIVED
STATE CORPORATION COMMISSION

OCT 20 1956

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

OCT 8 1956

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING

FILE SEC. 21 T. 20 R. 10W
BOOK PAGE 105 LINE 13