

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Rice County County. Sec. 17 Twp. 20S Rge. 10 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines App. 100/E. of

Lease Owner Glickman Oil Company

Lease Name Rick Well No. 4

Office Address Box 3104, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) D&A

Date well completed 12-6-65 19

Application for plugging filed 12-6-65 19

Application for plugging approved 12-6-65 19


Plugging commenced 12-6-65 19

Plugging completed 12-7-65 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Donald Triam

Producing formation Depth to top Bottom Total Depth of Well 3248' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	221'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to

feet for each plug set.
Mud up to 210' 1/4 sxs Hulls, Plug and 30 sxs cement through drill pipe.
Mud to 35' with plug & Hulls w/10 sxs cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glickman Oil Company

Address Box 3104, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Milton Glickman (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Milton Glickman
Box 3104, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of December, 1965

My commission expires November 17, 1967

Lorella Schauf
Lorella Schauf Notary Public.

GLICKMAN OIL COMPANY

15.159.30163.0000

P.O. Box 3104

Wichita, Kansas 67211

DRILLERS WELL LOG

Company: Glickman Oil Company

Location: App. 100' E. of
SW SE SE 17-20S-10W
Rice County, Kansas

Farm: Rick Well No. 4

Commenced: November 29, 1965

Elevation: 1788' KB

Completed: December 7, 1965

Total Depth: 3248'

Geologist: Robert G. Brooks

Casing: 10-3/4" @ 221' w/160 sxs

Production: D&A

Figures Indicate Bottom of Formations

30'	Sand & Shale
221'	Surface Clay & Shale
993'	Shale & Shells
1395'	Shale
1945'	Lime & Shale
2337'	Shale
2520'	Shale & Lime
2795'	Lime & Shale
2864'	Shale & Lime
3104'	Lime & Shale
3230'	Lime
3248'	Lime & Shale
3248'	Total Depth

TOPS	
Tarkio Lime	2297'
Tarkio Sand	2330'
Topeka	2613'
Heebner	2885'
Brown Lime	3012'
Lansing	3039'

RECEIVED
STATE CORPORATION COMMISSION

DEC 23 1965

CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss:

I, Milton Glickman, of the Glickman Oil Company, upon oath state that the above and foregoing is a true and correct copy of the log of the Rick #4

Milton Glickman

Subscribed and sworn to before me this 13th day of December, 1965

Lorella Schauf

Notary Public

My Commission Expires: November 17, 1967