

# WELL PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division,  
State Corporation Commission,  
800 Bitting Building,  
Wichita, Kansas.

## OR FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging of formations.

NORTH


Locate well correctly on above  
640 A. Plat

.....Ellis County. Sec. .... Twp. 37 Rge. (E) (W) .....

Lease Name.....Transwestern Oil Company.....

Lease Owner.....Transwestern Oil Company.....

Office Address.....Wichita, Kan......

Character of Well (Oil, Gas or Dry).....Oil..... Total Depth of Well.....193 Feet

Date, well, completed.....June 16th.....

Application for plugging and log of well filed.....June 16th..... 1937

Application for plugging approved.....June 16th..... 1937

Plugging Commenced.....June 18th..... 1937

Plugging Completed.....June 20th..... 1937

Reason for abandonment of well or producing formation.....Dry Hole.....

If a producing well is abandoned, date of last production.....1937.....

Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....Yes.....

Name of Conservation Officer who supervised plugging of this well.....J. A. Clendenen.....

Producing formation.....None.....

Show depth and thickness of all water, oil and gas formations.....None.....

### OIL, GAS OR WATER RECORDS

### CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
<u>Silicious Lims.</u>	<u>3'</u>	<u>3300'</u>	<u>3401</u>	<u>7" O.D.</u>	<u>3343</u>	<u>1400'</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

There was 7" wood plug drove on bottom, then cement with 10 sacks cement. Then filled 300' with mud from mud pits, the ripped 7" off at 1483' and pulled out and reamed hole. Bridged 10" hole @ 250' and cement with 10 sacks cement, then filled hole to bottom of collar.

**PLUGGING**  
FILE SEC 17T-2910W  
BOOK 94 LINE 24

(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations?.....Yes.....

Was exception made?..... If so describe.....Transwestern Oil Company.....

Correspondence regarding this well should be addressed to.....Box 1988, Wichita, Kansas.....

Address.....Wichita, Kansas.....

STATE OF.....Kansas..... COUNTY OF.....Ellis....., ss.

.....J. V. Williams..... (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature).....J. V. Williams.....  
.....Bushton Kans..... (Address)

SUBSCRIBED AND SWORN TO before me this.....30<sup>th</sup>..... day of.....July....., 1937.....

My commission expires.....June 29<sup>th</sup> 1938.....  
.....E. B. Mueggli..... Notary Public.

Casing RecordSW NW 17-20-10 W.  
Rice County, Kansas.10" 201'  
7" 3356'THOMPSON ESTATE #1Contractor: Iron Drilling Co.  
COMMENCED: March 10, 1937.  
Completed: June 10, 1937.  
Initial Prod: Dry  
Elevation: 1787

<u>FORMATION</u>	<u>DEPTH</u>
Cellar	0
Clay yellow	50
Water sand	65
Shale	90
Sand	100
Shale & Shells	202
Red bed	452
Shale & Shells	800
Shale & Salt	1230
Shale & Shells	1410
Lime & Shale	1540
Shale & Lime	1680
Shale & Shells	1775
Lime & Shale	1850
Shale & Lime	1929
Shale & Shells	2248
Shale & Shells	2305
Shale & Lime	2399
Shale & Shells	2505
Lime	2525
Lime & Shale	2629
Lime	2895
Shale & Lime	3010
K. C. Lime	3295
Lime	3318
Conglomerate	3365
Shale Green	3401

HFW - B &amp; A.

