

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

NORTH

X			

Locate well correctly on above
Section Plat

Rice County. Sec. 17 Twp. 20 Rge. 10 (E) W (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW NW NW
Lease Owner Branine-Holl
Lease Name Massman Well No. 2
Office Address 822 Central Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed June 7, 1950 19
Application for plugging filed July 9, 1950 19
Application for plugging approved July 9, 1950 19
Plugging commenced July 9, 1950 19
Plugging completed July 14, 1950 19
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee
Producing formation Depth to top Bottom Total Depth of Well 3336 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8	187'	
				5 1/2"	3335'	2479'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

3120			Set plug
3120	to	3100	Filled with sand
3100	to	3060	6 sacks cement
3060	to	170	Mudded
170	to	160	Rock bridge
160	to	125	15 sacks cement
125	to	20	Mudded
20	to	Cellar	6 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Branine-Holl
Address 822 Central Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Wilbur M. Ball (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed, and that the same are true and correct. So help me God.

(Signature) Wilbur M. Ball
822 Central Building, Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN to before me this 19th day of February, 1951

My commission expires July 19, 1952

22-7377-8 4-49-10M

Notary Public.

PLUGGING
FILE SEC 17 T 20 R 10 W
BOOK PAGE 46 LINE 31

WELL LOG OF MASSMAN NO. 2

BRANINE-HOLL

Commenced: June 1, 1950

Completed: June 9, 1950

Location: SW NW NW Sec. 17-20-10 W
Rice County, Kansas.

From	To	Formation	Remarks
0	187	Shale, shells & sand	Ran 9 Jts 8-5/8" Used Casing
187	660	Red bed, shale & shells	Cemented with 175 sacks Cement
660	1435	Shale & shells	Set at 187'
1435	1520	Lime & shale	
1520	1820	Lime	
1820	2185	Lime & shale	
2185	2335	Shale & lime	
2335	2383	Shale & shells	
2383	2410	Shale & lime	
2410	2560	Lime & shale	
2560	2980	Lime	
2980	3038	Shale	
3038	3321	Lime	
3321	3334	Shale & lime	
3334	3336	Corrected measurement	Ran 105 Jts 5 1/2" OD Casing
		Total Depth	Cemented with 125 sacks Cement
			Pipe set at 3335'

I certify the above and foregoing to be a true and exact copy of the original driller's log on the Massman # 2.

HERNDON DRILLING CO.

(Signed) By B. E. Rogers
Secretary-Treasurer

Subscribed and sworn to before me this 21st day of June, 1950

(Signed) Eloise Sterge
Notary Public

My commission expires Aug. 28, 1951

RECEIVED
STATE CORPORATION COMMISSION
FEB 20 1951
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 17-20-10
BOOK PAGE 16 LINE 31