

15.159.04516.0000

2-070579

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: NONE
NW, NW, SE, SECTION 21 TOWNSHIP 20 RANGE 10W

OPERATOR LICENSE # 30606 2310 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR MURFIN DRILLING CO. INC.
NAME & 250 N. WATER, #1300
ADDRESS WICHITA, KS 67202

Binger A Twin 2

LEASE NAME: BINGER #1
COUNTY: RC
WELL TOTAL DEPTH: 3428'
PIPE: NONE

SURFACE CASING: 8 5/8" @ 105'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: MIKES TESTING & SALVAGE
ADDRESS: BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:00 DAY: 23 MONTH: 10 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: MANNIE
COMPANY NAME: SAME PHONE: 316-
WERE: SAND TO 3240' & 5 XS., 35 XS. @ 1400', 100LBS. HULLS
35 XS. @ 900', 100LBS. OF HULLS 250' TO 0'.


PLUGGING PROPOSAL RECEIVED BY: MW
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 2:00 DAY: 23 MONTH: 10 YEAR: 1995

ACTUAL PLUGGING REPORT:
SANDED BOTTOM TO 3240' & 5 XS. OF COMMON SHOT 5 1/2"
CASING OFF @ 2220'. PULLED TO 1400' PUMPED 100LBS.
HULLS 35 XS. PULLED TO 900' PUMPED 100LBS. HULLS 35 XS.
PULLED TO 250' CIRC. CMT. TO SURFACE.

REMARKS: ALLIED #2866. 60/40 POZ. 4% GEL.

I DID OBSERVE THIS PLUGGING.


Jack Luth (AGENT)