

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita. KS 67202-1513

API Well Number: 15-205-28039-00-00
Spot: SWSWSWSE Sec/Twnshp/Rge: 6-29S-15E
295 feet from S Section Line, 2325 feet from E Section Line
Lease Name: TAYLOR Well #: 1H2S
County: WILSON Total Vertical Depth: 1163 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	8	20		8 SX
PROD	0	0		0 SX
SURF	8	20		8 SX

Well Type: ST UIC Docket No: _____ Date/Time to Plug: 09/10/2012 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JASON JOHN Company: WILSON COUNTY HOLDINGS Phone: (303) 884-3203

Proposed Plugging Method: Revised plugging procedure from well bottom: 100' cement at well bottom, water-based drilling mud plug 500' from bottom, 100' cement plug, water-based mud to 250' from well top elevation, and 250' cement plug to surface. After set, well is cut off at 4' below grade.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 09/10/2012 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The wellbore was gelled and then 25 sacks of cement spotted at 1135 ft. The 2.375 inch cement string was pulled to 635 ft and 25 sacks of cement spotted. The cement string was pulled to 250 ft and the well pumped full to surface. The cement string was removed and the well topped off with cement. A total of 125 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST #3
AUG 15 2018
CHANUTE, KS

AD

INVOICED

AUG 15 2018

Remarks:

Plugged through: OH

District: 03

Signed

Alan Dunning
(TECHNICIAN)