

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-28041-00-00
Spot: SENWSESW Sec/Twnshp/Rge: 6-29S-15E
886 feet from S Section Line, 1910 feet from W Section Line
Lease Name: TAYLOR Well #: 1H1S
County: WILSON Total Vertical Depth: 1135 feet

| Operator License No.: <u>34697</u> | String | Size | Depth (ft) | Pulled (ft) | Comments |
|--|--------|------|------------|-------------|----------|
| Op Name: <u>WILSON COUNTY HOLDINGS LLC</u> | COND | 8 | 20 | | 8 SX |
| Address: <u>1135 N. 15TH ST.</u> | PROD | 0 | 0 | | 0 SX |
| <u>FREDONIA, KS 66736</u> | SURF | 8 | 20 | | 8 SX |

Well Type: ST UIC Docket No: _____ Date/Time to Plug: 09/10/2012 10:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: JASON JOHN Company: WILSON COUNTY HOLDINGS Phone: (303) 884-3203

Proposed Plugging Method: Revised plugging procedure from well bottom: 100' cement at well bottom, water-based drilling mud plug 500' from bottom, 100' cement plug, water-based mud to 250' from well top elevation, and 250' cement plug to surface. After set, well is cut off at 4' below grade.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 09/10/2012 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

The wellbore was gelled using a 2.375 inch cement string. 25 sacks of cement were then spotted at TD. The cement string was pulled to 635 ft and 25 sacks of cement spotted. The cement string was pulled to 250 ft and the well pumped full. The cement string was removed and the well topped off with cement. A total of 125 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST # 3
AUG 15 2018
CHANUTE, KS

AD

INVOICED

AUG 15 2018

Remarks:

Plugged through: OH

District: 03

Signed

Alan Dunning

(TECHNICIAN)