

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-23458-00-00
Spot: NENWNWSE Sec/Twnshp/Rge: 1-29S-14E
2475 feet from S Section Line, 2090 feet from E Section Line
Lease Name: ARTHUR C. CLARY Well #: 2
County: WILSON Total Vertical Depth: 1150 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	1100		100 SX
SURF	7	20		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/17/2017 10:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Revd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run one inch to TD of well and pump cement to surface. Trip out and top well off than cut off below plow depth.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 07/17/2017 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

The wellhead was connected to directly and circulation established by pumping 5 bbls of water. The well was then pumped full of cement and cottonseed hulls by squeezing and shut in with 600 psi. A total of 42 sacks of portland cement were used to plug well.

Perfs:

RECEIVED
KCC DIST # 3
AUG 14 2018
CHANUTE, KS

AD

INVOICED
AUG 15 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)