

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-24899-00-01  
Spot: SWSENESE Sec/Twnshp/Rge: 1-29S-14E  
1500 feet from S Section Line, 600 feet from E Section Line  
Lease Name: ARTHUR C CLARY Well #: 9  
County: WILSON Total Vertical Depth: 1100 feet

Operator License No.: 34697  
Op Name: WILSON COUNTY HOLDINGS LLC  
Address: 1135 N. 15TH ST.  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	1140		100 SX
SURF	7	40		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2017 3:00 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Hook on to wellhead and establish circulation then pump 15ppg cement until well pressures up shut in and come back next day to cut below plow depth.

Plugging Proposal Received By: ALAN DUNNING Witness Type: NONE  
Date/Time Plugging Completed: 06/15/2017 3:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

After a packer and 100 ft of 1 inch were removed, the well was connected to directly and circulation established by pumping 5 bbls of water. The well was then pumped full of 56 sacks of cement but would not hold pressure. Came back the next day and tagged cement at 600 ft. The well was then pumped full from 600 ft to surface thru a cement string. A total of 84 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
822	828		

RECEIVED  
KCC DIST # 3  
AUG 14 2018  
CHANUTE, KS

AD

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)