

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-01244-00-00

Spot: NENESWSW

Sec/Township/Rge: 6-29S-15E

1264 feet from S Section Line, 4087 feet from E Section Line

Lease Name: HENDRY

Well #: 2

County: WILSON

Total Vertical Depth: 830 feet

Operator License No.: 34697

Op Name: WILSON COUNTY HOLDINGS LLC

Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	830		145 SX
SURF	8	25		10 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 11/16/2017 8:00 AM

Plug Co. License No.: 33749

Plug Co. Name: KEPLEY WELL SERVICE, LLC

Proposal Revd. from: FORREST SUTHERLAND

Company: WILSON COUNTY HOLDINGS

Phone: (620) 325-4344

Proposed
Plugging
Method:

Drill on hole until TD is reached and run 1" pipe to TD of hole and pump cement to surface than trip pipe out and top well off.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: NONE

Date/Time Plugging Completed: 11/16/2017 8:00 AM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

The wellhead was hooked onto directly and circulation established by pumping 12.5 bbls of water. The well was then pumped full of cement and cottonseed hulls by squeezing. The well was shut in with 800 psi. A total of 101 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
815	820		

RECEIVED
KCC DIST # 3
AUG 14 2018
CHANUTE, KS

AD

INVOICED

AUG 15 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)