

15.083.10180.0001

1060200

STATE CORPORATION COMMISSION

API NUMBER 15-083-20,849-0001
C NE NW SEC. 17, T 21 S, R 22 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME ANTRIM WELL # 1

TECHNICIAN'S PLUGGING REPORT

2/22

COUNTY HODGEMAN

143.98

OPERATOR LICENSE # 4058

WELL TOTAL DEPTH 4430 FEET

OPERATOR: AMERICAN WARRIOR, INC.

PRODUCTION CSG: SIZE 4 1/2" @ 4425' WITH 130 SX

NAME AND PO BOX 399

SURFACE CASING: SIZE 8 5/8" @ 269' WITH SX

ADDRESS GARDEN CITY, KS 67846

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D-20,956 D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SWIFT SERVICES INC. LICENSE NUMBER 32382

ADDRESS PO BOX 466 NESS CITY, KS 67560

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 22 MONTH: 02 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM

(COMPANY NAME) SWIFT SERVICES INC. (PHONE) 785-798-2300

WERE: PERFS AT 910-960

RUN TUBING TO 800' MIXED 60 SX CEMENT WITH 400# HULLS TILL CIRCULATED, THEN PULLED TUBING AND TOPPED OFF WITH 10 SX CEMENT. WENT DOWN BACKSIDE WITH 40 SX CEMENT. PRESSURED TO 400# AND HELD.

PLUGGING PROPOSAL RECEIVED BY MIKE MAIER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 22 MONTH: 02 YEAR: 2000

ACTUAL PLUGGING REPORT

RUN TUBING TO 800' MIXED 60 SX CEMENT WITH 400# HULLS TILL CIRCULATED. THEN PULLED TUBING AND TOPPED OFF WITH 10 SX CEMENT. WENT DOWN BACKSIDE WITH 40 SX CEMENT. PRESSURED TO 400# AND HELD.

RECEIVED
STATE CORPORATION COMMISSION

MAR - 1 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY SWIFT SERVICES. NO CASING RECOVERED.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

SIGNED

Michael J. Pierfer
(TECHNICIAN)

DATE 3/1/00

FORM CP-2/3

WV. NO. 061349

(R)