

TO:  
 STATE CORPORATION COMMISSION  
 CONSERVATION DIVISION - PLUGGING  
 266 N. Main St., Ste. 220  
 Wichita, KS 67202-1513

API Well Number: 15-135-25773-00-00  
 Spot: NWNWENW Sec/Twnshp/Rge: 24-19S-23W  
133 feet from N Section Line, 1503 feet from W Section Line  
 Lease Name: ERB UNIT Well #: 1-24  
 County: NESS Total Vertical Depth: 4475 feet

Operator License No.: 5144  
 Op Name: MULL DRILLING COMPANY, INC.  
 Address: 1700 N WATERFRONT PKWY BLDG 120  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3955		
CIBP		4316		
PC		1537		WITH 165 SX CMT. 15 SX CMT CIRCULATED TO PIT.
PROD	5.5	4470	0	WITH 150 SX CMT
SURF	8.625	218		WITH 165 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/07/2018 9:30 AM  
 Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.  
 Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-0591

Proposed Plugging Method: PUMP 35 SX CMT ON BOTTOM WITH 150# HULLS. SPACER TO ANHYDRITE. CMT TO SURFACE. 50 SX CMT FOR BACKSIDE.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
 Date/Time Plugging Completed: 08/07/2018 11:15 AM KCC Agent: ERIC MACLAREN

**Actual Plugging Report:**

TIED ONTO THE CASING & ESTABLISHED A PUMP RATE OF 3 1/2 BPM AT 800#. TIED ONTO THE BACKSIDE & PUMPED 10 SX CMT PRESSURING TO 300#. TIED ONTO THE CASING & PUMPED 50 SX CMT WITH 200# HULLS, 44 BBL GEL WATER SPACER TO 1550' & 150 SX CMT TO SURFACE. PRESSURED UP TO 1500# & SHUT IN AT 500#.

**Perfs:**

Top	Bot	Thru	Comments
4346	4355		
3960	3966		
3942	3946		

INVOICED  
 AUG 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

District: 01

RECEIVED  
 AUG - 8 2018  
 KCC DODGE CITY

Signed [Signature]  
 (TECHNICIAN)

RECEIVED  
 KANSAS CORPORATION COMMISSION  
 AUG 15 2018  
 CONSERVATION DIVISION  
 WICHITA, KS