

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-025-20188-00-01
Spot: SENWNWNW Sec/Twnshp/Rge: 33-30S-23W
4639 feet from S Section Line, 4818 feet from E Section Line
Lease Name: ALLEN D OWWO Well #: 1
County: CLARK Total Vertical Depth: 4942 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 120
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4620		WITH 2 SX CMT
PROD	4.5	4754	2196	
SURF	8.625	356		WITH 175 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/01/2018 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: TIM HOSS Company: MULL DRILLING Phone: (316) 734-6768

Proposed Plugging Method: CIBP WITH 2 SX CMT OR 25 SX CMT WITH HULLS. CUT & PULL CASING. PLUG AT 1500' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL
Date/Time Plugging Completed: 08/02/2018 10:00 AM KCC Agent: LARRY HARRIS

Actual Plugging Report:

8/1/18: SET CIBP @ 4620' WITH 2 SX CMT. 1ST PLUG AT 1500' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400'. PUMPED 50 SX CMT BUT HAD NO CIRCULATION. SHUT DOWN TO TAG. 8/2/18: TAGGED CMT AT 350'. CIRCULATED CMT TO SURFACE WITH 75 SX CMT. PULLED CASING & TOPPED OFF WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4670	4672		

INVOICED

AUG 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG - 6 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 15 2018
CONSERVATION DIVISION
WICHITA, KS