

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22486-00-00
Spot: NESE Sec/Twnshp/Rge: 14-33S-13W
2053 feet from S Section Line, 659 feet from E Section Line
Lease Name: ANGELL C Well #: 4
County: BARBER Total Vertical Depth: 5015 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4440		WITH 2 SX CMT
PROD	5.5	5004	2100	WITH 230 SX CMT
SURF	8.625	441		WITH 285 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/02/2018 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: HERMAN L. LOEB LLC Phone: (620) 886-2419

Proposed Plugging Method: SET CIBP @ 4440' WITH 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/02/2018 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4440' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 628' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 469' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 50 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4484	4516		

INVOICED
AUG 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed

Stephan J. Pfeifer
(TECHNICIAN)

RECEIVED
AUG - 7 2018
KCC DODGE CITY

5A

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

AUG 15 2018

CONSERVATION DIVISION
WICHITA, KS