

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-22035-00-00
Spot: NESWSESE Sec/Twnshp/Rge: 18-22S-33W
333 feet from S Section Line, 971 feet from E Section Line
Lease Name: GARDEN CITY Well #: 3-18
County: FINNEY Total Vertical Depth: 4850 feet

Operator License No.: 5210
Op Name: LEBSACK OIL PRODUCTION INC.
Address: P.O. BOX 159
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4110		WITH 2 SX CMT
CIBP		4730		
PROD	4.5	4845	0	WITH 135 SX CMT
SURF	8.625	485		WITH 300 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/01/2018 9:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: BERT MASTIN Company: LEBSACK OIL Phone: (620) 234-5191

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 08/01/2018 9:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FROM 9-29-09 TO 10-1-09 THE WELL WAS PERFORATED AT 1150', 1101', 1000', 750', & 650'. EACH INTERVAL WAS SQUEEZED IN ATTEMPT TO CIRCULATE CMT TO SURFACE. A TOTAL OF 600 SX CMT WAS USED & CMT WAS CIRCULATED TO SURFACE. CIBP @ 4110' WITH 2 SX CMT. TEST CASING TO 1000#. PERFORATE 4 HOLES AT 2000'. INJECTION RATE 2 BPM AT 1300#. RUN TBG & PACKER TO 1500'. SPOT 50 SX CMT HALF IN AND HALF OUT OF THE PERFS. RUN TBG TO 1100' & CIRCULATE CMT TO SURFACE WITH 75 SX CMT. TOOH WITH TBG & TOP OFF WITH 15 SX CMT. 5 SX CMT DOWN THE ANNULUS TO 250#.

Perfs:

Top	Bot	Thru	Comments
4768	4772		
4730			
4671	4673		
4654	4671		

INVOICED


AUG 16 2018

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED 60/40 POZMIX 4% GEL BY BASIC.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG 13 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 15 2018

CONSERVATION DIVISION
WICHITA, KS