

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23427-00-00
Spot: N2NWSE Sec/Twnshp/Rge: 13-24S-14W
2325 feet from S Section Line, 2029 feet from E Section Line
Lease Name: HARRISON Well #: 5-13
County: STAFFORD Total Vertical Depth: 4070 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S MAIN ST
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3570		WITH 2 SX CMT
CIBP		3800		
PROD	5.5	4017	3022	WITH 125 SX CMT
SURF	8.625	828		WITH 450 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/09/2018 12:10 PM
Plug Co. License No.: 7868 Plug Co. Name: KIZZAR WELL SERVICING, INC.
Proposal Rcvd. from: RANDY GNEIST Company: RAMA OPERATING Phone: (620) 234-5191

Proposed Plugging Method: SET CIBP @ 3570' WITH 2 SX CMT. PLUG AT 870' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/09/2018 2:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

CIBP @ 3570' WITH 2 SX CMT ON TOP. 1ST PLUG AT 870' LOAD HOLE, BREAK CIRCULATION, PUMP 10 SX GEL & 50 SX CMT. 2ND PLUG AT 330' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT. HOLE STAYING FULL.

Perfs:

Top	Bot	Thru	Comments
3908	3920		
3614	3752		

INVOICED
AUG 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

Signed _____

RECEIVED
AUG 14 2018
KCC DODGE CITY

(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

AUG 15 2018
Dodge City 2/3

CONSERVATION DIVISION
WICHITA, KS