

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-20092-00-00
Spot: SWSENE Sec/Twnshp/Rge: 36-34S-31W
4252 feet from S Section Line, 406 feet from E Section Line
Lease Name: ADAMS Well #: 2
County: SEWARD Total Vertical Depth: 4400 feet

Operator License No.: 35031
Op Name: R. C. TAYLOR OPERATING COMPANY
Address: 5661 N. CLASSEN BLVD
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4380	1347	WITH 125 SX CMT
SURF	8.625	1279		WITH 550 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2018 2:00 PM
Plug Co. License No.: 34199 Plug Co. Name: RAWHIDE WELL SERVICE, LLC
Proposal Rcvd. from: JARED NIX Company: RAWHIDE WELL SERVICE, LLC Phone: (307) 587-0090

Proposed Plugging Method: SET CIBP @ 4275' WITH 2 SX CMT. CUT CASING AT 1350'+ & PULL. RTIH. PLUG AT 1320' WITH 10 SX GEL & 50 SX CMT. PLUG AT 570' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT TO 0'.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: PARTIAL
Date/Time Plugging Completed: 08/06/2018 4:00 PM KCC Agent: HEITH WALSH

Actual Plugging Report:

RTIH TO 4275' & PUMPED 30 SX CMT & 200# HULLS. 1ST PLUG AT 1320' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 570' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 8/3/18: TAG TOC @ 184'. 8/6/18: RTIH TO 180'. 4TH PLUG AT 180' TO 0' WITH 90 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4312	4328		

INVOICED
AUG 16 2018

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
AUG - 9 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 15 2018
CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3