

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-033-21303-00-00  
Spot: NESENEW Sec/Twnshp/Rge: 19-33S-19W  
786 feet from N Section Line, 2660 feet from E Section Line  
Lease Name: BAKER FARMS Well #: 2  
County: COMANCHE Total Vertical Depth: 5440 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5250		WITH 10 SX CMT
COND	13.375	91		WITH 100 SX CMT
PROD	4.5	5436	1836	WITH 100 SX CMT
SURF	8.625	803		WITH 325 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/07/2018 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5250' WITH 10 SX CMT. PLUG AT 960' WITH 75 SX CMT. PLUG AT 360' WITH 40 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: NONE  
Date/Time Plugging Completed: 08/07/2018 2:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5250'. CIRCULATED HOLE WITH 85 BBL MUD THEN SPOTTED 10 SX CMT ON TOP OF CIBP. 1ST PLUG AT 960' WITH 75 SX CMT. 2ND PLUG AT 360' WITH 40 SX CMT. 3RD PLUG AT 64' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5356	5360		
5300	5302		

INVOICED  
AUG 16 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed [Signature] ECRS RECEIVED  
(TECHNICIAN) KANSAS CORPORATION COMMISSION

RECEIVED  
AUG 14 2018  
KCC DODGE CITY

AUG 15 2018  
Form CP-273  
CONSERVATION DIVISION  
WICHITA, KS