

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-025-20875-00-00  
Spot: NENE Sec/Twnshp/Rge: 8-35S-25W  
4620 feet from S Section Line, 660 feet from E Section Line  
Lease Name: THEIS W. Well #: 3-8  
County: CLARK Total Vertical Depth: 6300 feet

Operator License No.: 34192  
Op Name: SANDRIDGE EXPLORATION AND PRO  
Address: 123 ROBERT S. KERR AVE  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	6299	1808	WITH 300 SX CMT
SURF	9.625	804		WITH 500 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2018 10:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5900' WITH 10 SX CMT. PLUG AT 1060'-700' WITH 100 SX CMT. PLUG AT 400'-250' WITH 40 SX CMT. PLUG AT 64'-4' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/13/2018 12:00 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

8/9/18: PARTED TBG. FISHED TO 4315'. SPOTTED 50 SX CMT WITH 100# HULLS.  
8/10/18: TAGGED TOC @ 4195'. 8/13/18: 1ST PLUG AT 1060' WITH 100 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 60' TO SURFACE WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5954	5979		

INVOICED  
AUG 16 2018

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed Larry Harris EPRS  
(TECHNICIAN)

RECEIVED  
AUG 14 2018  
KCC DODGE CITY

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 15 2018

CONSERVATION DIVISION  
WICHITA, KS