

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-033-21698-01-00
Spot: SESWSWSW Sec/Twnshp/Rge: 21-33S-19W
179 feet from S Section Line, 4634 feet from E Section Line
Lease Name: LINDSAY 3319 Well #: 1-21H
County: COMANCHE Total Vertical Depth: 5372 feet

Operator License No.: 34192
Op Name: SANDRIDGE EXPLORATION AND PRO
Address: 123 ROBERT S. KERR AVE
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5360		WITH 50 SX CMT
COND	20	120		WITH 12 YDS CMT
	L1 4.5	9765		TOP OF LINER 5425'
PROD	7	5815	1716	WITH 300 SX CMT
SURF	9.625	910		WITH 670 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/25/2018 10:00 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIP @ 5360' WITH 50 SX CMT. CIRCULATE HOLE WITH MUD. PLUG AT 960' WITH 80 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 64' WITH 30 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 07/26/2018 4:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5360'. CIRCULATED HOLE WITH 200 BBL MUD THEN SPOTTED 50 SX CMT ON TOP OF CIBP. 1ST PLUG AT 960' WITH 80 SX CMT. 2ND PLUG AT 320' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 30 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
9338	9659		
8880	9248		
8468	8812		
8042	8375		
7688	7940		
7192	7525		
6748	7098		
6323	6654		
5938	6225		
5494	5825		

INVOICED
AUG 16 2018

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES. TMD= 9765'

Plugged through: TBG

District: 01

RECEIVED
AUG - 6 2018
KCC DODGE CITY

Signed _____

RECEIVED
KANSAS CORPORATION COMMISSION

(TECHNICIAN)

AUG 15 2018

CONSERVATION DIVISION
WICHITA, KS