

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23494-00-00
Spot: E2NWNSE Sec/Twnshp/Rge: 21-34S-11W
2214 feet from S Section Line, 778 feet from E Section Line
Lease Name: DIEL & CO Well #: 4-21
County: BARBER Total Vertical Depth: 4775 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4550		WITH 2 SX CMT
COND	13.875	55		WITH 65 SX CMT
PROD	5.5	4772	3006	WITH 100 SX CMT
SURF	8.625	210		WITH 190 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/24/2018 2:30 PM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: DEON HOWARD Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: SET CIBP @ 4554' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 40' TO SURFACE WITH CMT.

Plugging Proposal Received By: LARRY HARRIS WitnessType: PARTIAL
Date/Time Plugging Completed: 07/24/2018 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4550' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 590' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 253' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4624	4629		
4604	4629		

INVOICED

AUG 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

RECEIVED
AUG - 7 2018
KCC DODGE CITY

AUG 15 2018
Form CP-2/3
CONSERVATION DIVISION
WICHITA, KS