

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-23531-00-00
Spot: S2N2NESW Sec/Twnshp/Rge: 16-34S-11W
2145 feet from S Section Line, 1980 feet from W Section Line
Lease Name: STAN MICHEL Well #: 5-16
County: BARBER Total Vertical Depth: 4753 feet

Operator License No.: 5822
Op Name: VAL ENERGY, INC.
Address: 125 N MARKET ST STE 1110
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4540 | | WITH 2 SX CMT |
| PROD | 5.5 | 4744 | 2978 | WITH 100 SX CMT |
| SURF | 8.625 | 211 | | WITH 190 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/26/2018 11:59 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: DEON HOWARD Company: VAL ENERGY Phone: (316) 263-6688

Proposed Plugging Method: CIBP @ 4540' WITH 2 SX CMT. PLUG AT 600' WITH 10-15 SX GEL & 50 SX CMT. PLUG AT 250' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 07/26/2018 3:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

SET CIBP @ 4540' WITH 2 SX CMT. 1ST PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 270' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4637 | 4641 | | |
| 4628 | 4634 | | |
| 4616 | 4624 | | |
| 4597 | 4641 | | |

INVOICED
AUG 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED
JUL 27 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 15 2018
CONSERVATION DIVISION
WICHITA, KS