

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-171-21228-00-00
Spot: SENESWNE Sec/Twnshp/Rge: 18-16S-31W
1840 feet from N Section Line, 1436 feet from E Section Line
Lease Name: BLACK KETTLE Well #: 1-18
County: SCOTT Total Vertical Depth: 4675 feet

Operator License No.: 3532

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF | 8.625 | 305 | | 210 SX |

Op Name: CMX, INC.

Address: 1700 N WATERFRONT PKWY BLDG 300
WICHITA, KS 67206

Well Type: DH

UIC Docket No:

Date/Time to Plug: 07/24/2018 12:00 AM

Plug Co. License No.: 5929

Plug Co. Name: DUKE DRILLING CO., INC.

Proposal Rcvd. from: DEON VASQUEZ

Company: DUKE DRILLING CO., INC.

Phone: (316) 267-1331

Proposed
Plugging
Method:

1ST PLUG AT 2340' WITH 50 SX-CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN

WitnessType: NONE

Date/Time Plugging Completed: 07/24/2018 12:00 AM

KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:


1ST PLUG AT 2340' WITH 50 SX CMT. 2ND PLUG AT 1650' WITH 80 SX CMT. 3RD PLUG AT 800' WITH 40 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY BASIC.

Plugged through: DP

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG - 7 2018
KCC DODGE CITY



RECEIVED
KANSAS CORPORATION COMMISSION

AUG 15 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3

INVOICED
AUG 16 2018