

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-135-25807-00-00  
Spot: SWSENWSE Sec/Twnshp/Rge: 2-20S-22W  
1528 feet from S Section Line, 1697 feet from E Section Line  
Lease Name: DECHANT BROTHERS Well #: 1  
County: NESS Total Vertical Depth: 4510 feet

Operator License No.: 33922  
Op Name: MUSTANG ENERGY CORPORATION  
Address: PO BOX 1121  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4360		
PC		1466		WITH 185 SX CMT TO 0'
PROD	5.5	4497	0	WITH 200 SX CMT
SURF	8.625	221		WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/08/2018 9:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Revd. from: ROD BRIN Company: MUSTANG ENERGY CORPORATIO Phone: (785) 623-0533

Proposed Plugging Method: SQUEEZE PERFS WITH 25 SX CMT WITH 200# HULLS. PUMP GEL SPACER TO 1500' & CIRCULATE CMT TO 0'. CHECK BACKSIDE WITH CMT TO 500 PSI.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/08/2018 11:10 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TIED ONTO THE CASING & PUMPED 25 SX CMT WITH 200# HULLS, 24 BBL MUD SPACER TO 1500' THEN 125 SX CMT TO SURFACE. PRESSURED TO 1000# & SHUT IN AT 700#. THE BACKSIDE SWEDGE & VAVLE WERE FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
4422	4427		
4412	4417		
4327	4332		

INVOICED

AUG 16 2018

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OILWELL CEMENTING.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
AUG 14 2018  
KCC DODGE CITY

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 15 2018  
Form CP-2/3  
CONSERVATION DIVISION  
WICHITA, KS