

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-20843-00-00
Spot: NENWSENW Sec/Twnshp/Rge: 12-29S-14E
3860 feet from S Section Line, 1760 feet from W Section Line
Lease Name: DOANE Well #: D1
County: WILSON Total Vertical Depth: 1170 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1050		185 SX
SURF	8.625	25		13 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/01/2016 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Revd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run one inch to TD of well and pump 15 ppg cement to surface than trip out and top well off.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 12/01/2016 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A one inch cement string was washed to 625 ft. Began pumping cement but cement did not come to surface. Pull out cement string. Came back the next day and tagged cement at 225 ft. The well was then pumped full from 225 ft to surface. A total of 123 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST # 3
AUG 17 2018
CHANUTE, KS

AD


INVOICED
AUG 17 2018

Remarks:

Plugged through: CSG

District: 03

Signed


(TECHNICIAN)