

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-19662-00-00
Spot: SENESE Sec/Twnshp/Rge: 1-29S-14E
2300 feet from S Section Line, 300 feet from E Section Line
Lease Name: ARTHUR C CLARY Well #: 0W
County: WILSON Total Vertical Depth: 1150 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.375	1100		95 SX
SURF	7	20		10 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/28/2016 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run 1" to TD of well and pump cement to surface. Trip out and top well off than cut below plow depth and bury.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 11/28/2016 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A one inch cement string was ran to TD. Begin pumping cement but would not circulate to surface. Pull one inch. Came back the next day and tagged cement at 400 ft. The well was then pumped full of cement from 400 ft to surface. The cement string was pulled and the well topped off with cement. A total of 77 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST # 3
AUG 17 2018
CHANUTE, KS

AD

INVOICED

AUG 17 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)