

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-22570-00-02
Spot: SWNE Sec/Twnshp/Rge: 1-29S-14E
4580 feet from S Section Line, 900 feet from E Section Line
Lease Name: DOCIA BATES Well #: 9
County: WILSON Total Vertical Depth: 1082 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	2.875	1078		99 SX
PROD	2.875	1082		
SURF	5	40		11 SX
SURF	5.5	50		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/18/2016 10:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: FORREST SUTHERLAND Company: WILSON COUNTY HOLDINGS Phone: (620) 325-4344

Proposed Plugging Method: Run 1" to TD of well and pump 15ppg portland cement to surface. Trip pipe out and top well off at surface.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 05/18/2016 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Tried to establish circulation but could not. A one inch cement string was lowered to 1060 ft inside the production pipe and the well pumped full of cement from btm to top. A total of 42 sacks of portland cement were used to plug well.

Perfs:

Top	Bot	Thru	Comments
977	983		

RECEIVED
KCC DIST # 3
AUG 17 2018
CHANUTE, KS

AD

INVOICED
AUG 17 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)