

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-28043-00-00
Spot: SWSENE Sec/Twnshp/Rge: 1-29S-14E
1100 feet from N Section Line, 365 feet from E Section Line
Lease Name: DOCIA BATES Well #: 1S
County: WILSON Total Vertical Depth: 1163 feet

Operator License No.: 34697
Op Name: WILSON COUNTY HOLDINGS LLC
Address: 1135 N. 15TH ST.
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	8	20		SX
PROD	0	0		0 SX
SURF	8	20		8 SX

Well Type: SI UIC Docket No: _____ Date/Time to Plug: 09/19/2012 12:00 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: DONALD MISSEY Company: WILSON COUNTY HOLDINGS Phone: (303) 884-3203

Proposed Plugging Method: Plugging procedure from well bottom: 100' cement at well bottom, water-based drilling mud plug 500' from bottom, 100' cement plug, water-based mud to 250' from well top elevation, and 250' cement plug to surface. After set, well is cut off at 4' below grade.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 09/19/2012 12:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 2.375 inch cement string was lowered to 1160 ft and 25 sacks of cement spotted. The cement string was pulled to 585 ft and 25 sacks of cement spotted. The cement string was pulled to 250 ft and the well pumped full. Gel spacers were used between cement plugs. A total of 125 sacks of portland cement were used to plug well.

RECEIVED
KCC DIST # 3
AUG 17 2018
CHANUTE, KS

AD

Remarks:

Plugged through: OH

District: 03

Signed

Alan M. Dunning
(TECHNICIAN)