

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-071-20152-00-00
Spot: NW Sec/Twnshp/Rge: 34-20S-39W
3968 feet from S Section Line, 3884 feet from E Section Line
Lease Name: KAISER Well #: 1
County: GREELEY Total Vertical Depth: 2840 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2835		WITH 450 SX CMT
SURF	8.625	248		WITH 250 SX CMT

Well Type: GAS - (oil) UIC Docket No: _____ Date/Time to Plug: 08/13/2018 11:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: WELD ON 4 1/2" COLLAR & 4 1/5" X 8 5/8" DONUT. RUN SANDLINE WITH DEPTHOMETER TO CHECK FOR BRIDGE & TD. SET CIBP @ 2400' WITH 2 SX CMT. ATTEMPT TO LOAD 4 1/2" CASING & TEST TO 500 PSI. RUN CBL TO DETERMINE CMT TOP. IF NO CMT ACROSS THE USABLE WATER, PERFORATE 4 HOLES AT 1300' & PUMP 80 SX CMT 1/2 IN & 1/2 OUT OF THE 4 1/2" CASING WITH HULLS IN THE LAST 40 SX CMT. IF THERE IS CMT ACROSS THE USABLE WATER, BUT NOT ACROSS THE BOTTOM OF THE SURFACE CASING PERFORATE 4 HOLES AT 280' THEN RUN TBG TO 1300'. FILL THE 4 1/2" CASING WITH CMT UP TO 280' THEN FILL THE 4 1/2" AND 4 1/2" X 8 5/8" WITH CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2018 3:00 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

Perfs:

8/10/18: RIGGED UP & RAN BAILER ON SANDLINE AND STACKED OUT AT 1490'. RAN CBL TOOL & GOT TO 1906'. LOADED HOLE WITH WATER & RAN CBL FROM 1906' TO SURFACE. FOUND TOC @ 50'. 8/13/18: RAN 2 3/8" TBG TO 1930' IN 4 1/2" CASING. RAN 1" TBG DOWN 4 1/2" X 8 5/8" ANNULUS TO 36' & CIRCULATED FULL WITH 10 SX CMT. TIED ON TO 2 3/8" TBG & PUMPED 135 SX CMT WITH 3% CC & 150# HULLS CIRCULATING TO SURFACE. RAN TBG OUT OF CASING & TOPEED OFF 4 1/2" WITH 30 SX CMT. HOLE STAYING FULL.

Top	Bot	Thru	Comments
2804	2811		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE. CONTROL # 20180032

Plugged through: TBG

District: 01

Signed _____

(TECHNICIAN)

RECEIVED
AUG 14 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 15 2018

CONSERVATION DIVISION
WICHITA, KS