

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20216-00-00
Spot: NE Sec/Twnshp/Rge: 18-23S-41W
3957 ~~4103~~ feet from S Section Line, 1240 feet from E Section Line
Lease Name: SHAFER 1169 Well #: 1
County: HAMILTON Total Vertical Depth: 2568 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2000		WITH 2 SX CMT
PROD	4.5	2571	0	WITH 500 SX CMT
SURF	8.625	331		WITH 250 SX CMT

Well Type: GAS - (Oil) UIC Docket No: _____ Date/Time to Plug: 08/08/2018 3:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: WELD ON 4 1/2" COLLAR & 4 1/2" X 8 5/8" DONUT OVER ANNULUS. RAN SAND LINE WITH DEPTHOMETER & CHECK FOR OBSTRUCTIONS & FILL UP. SET CIBP @ APP. 2000' WITH 2 SX CMT. LOAD HOLE WITH WATER & RUN CBL TO DETERMINE TOC. IF NO CMT AT 1030', PERFORATE 4 HOLES & SPOT 80 SX CMT HALF IN & HALF OUT PERFS WITH HULLS IN LAST 40 SX CMT. IF THERE IS CMT AT 1130', NO NEED TO PERFORATE. IF NO CMT AT 360', PERFORATE 4 HOLES. RUN TBG TO 1030' & FILL 4 1/2" WITH CMT UP TO 360' THEN FILL 4 1/2" & 4 1/2" X 8 5/8" ANNULUS WITH CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2018 10:30 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

8/9/18: CIBP @ 2000' WITH 2 SX CMT. LOAD HOLE & RAN CBL FROM 1810' TO 20'. TOC @ 67'. TIH WITH TBG TO 1023'. 8/10/18: RUN 1" DOWN THE 4 1/2" X 8 5/8" ANNULUS & TAGGED CMT AT 55'. CIRCULATE CMT TO SURFACE WITH 15 SX CMT. TBG SET AT 1023'. CIRCULATE CMT TO SURFACE INSIDE THE 4 1/2" CASING WITH 75 SX CMT. TOOH & TOP OFF CASING WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2508	2516		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY. CONTROL# 20180030

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG 13 2018
KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 15 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3