

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-075-20314-00-00
Spot: NWNWNWSE Sec/Twnshp/Rge: 19-22S-42W
2564 feet from S Section Line, 2517 feet from E Section Line
Lease Name: SIMON Well #: 1
County: HAMILTON Total Vertical Depth: 2800 feet

Operator License No.: 101
Op Name: KCC FEE FUND PLUG
Address: 266 N MAIN ST, STE 220
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1200		
CIBP		2100		WITH 2 SX CMT
PROD	4.5	2805	0	WITH 350 SX CMT
SURF	7	547		WITH 300 SX CMT

Well Type: GAS (Oil) UIC Docket No: _____ Date/Time to Plug: 07/24/2018 1:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SET CIBP @ 2100' WITH 2 SX CMT. LOAD HOLE & RUN CBL TO DETERMINE TOC. TEST CASING TO 500#. IF USABLE WATER IS NOT COVERED WITH CMT, PERFORATE 4 HOLES & PUMP 80 SX CMT 1/2 IN & 1/2 OUT OF THE 4 1/2" WITH HULLS IN THE LAST 40 SX CMT. IF USABLE WATER IS COVERED WITH CMT BUT THE BOTTOM OF THE SURFACE CASING IS NOT PERFORATE 4 HOLES AT 600'. RUN TBG TO 1200' & FILL THE 4 1/2" CASING WITH CMT UP TO 600' THEN FILL THE 4 1/2" & 4 1/2" X 8 5/8" WITH CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/07/2018 6:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2100' WITH 2 SX CMT. (FLUID LEVEL= 560' FROM SURFACE) RAN CBL FROM 1820' TO 570'. FOUND TOC AT 1032'. USABLE WATER IS COVERED. SET CIBP @ 1200' OVER CASING LEAK. LOAD CASING & PRESSURE TEST TO 600#. HOLDING. PERFORATE 4 HOLES AT 575'. INJECTION RATE 4 BPM AT 0 PSI. RUN TBG TO 1200' & CIRCULATE CMT TO SURFACE UP THE 4 1/2" CASING & 4 1/2" X 7" ANNULUS WITH 165 SX CMT. TOOH WITH TBG & TOP OFF WITH 5 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2580	2586		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE. CONTROL # 20180031
Plugged through: TBG

District: 01

RECEIVED
AUG 13 2018
KCC DODGE CITY

Signed Ken Jehlik
RECEIVED
KANSAS CORPORATION COMMISSION (TECHNICIAN)
AUG 15 2018