

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-145-20808-00-00

Spot: NE

Sec/Twnshp/Rge: 24-20S-19W

3676

3980 feet from S Section Line, 1309 feet from E Section Line

Lease Name: STARMER

1306 Well #: 1-24

County: PAWNEE

Total Vertical Depth: 2385 feet

Operator License No.: 101

String Size Depth (ft) Pulled (ft) Comments

Op Name: KCC FEE FUND PLUG

PROD 4.5 2385 0 WITH 425 SX CMT

Address: 266 N MAIN ST, STE 220

SURF 7 988 WITH 300 SX CMT

WICHITA, KS 67202

Well Type: GAS (OIL)

UIC Docket No:

Date/Time to Plug: 07/20/2018 12:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: RICHARD MCINTYRE

Company: QUALITY WELL SERVICE, INC.

Phone: (620) 727-3410

Proposed Plugging Method: RUN SAND LINE TO CHECK FOR FILL UP & OBSTRUCTIONS. LOAD HOLE & PRESSURE TEST CASING. RUN BOND LOG. IF CASING TESTS & TOC IS BELOW 500', PERFORATE AT 600'. RUN TBG TO 1300' & PUMP 20 SX CMT. PULL TO 600' & CIRCULATE INSIDE & OUT TO SURFACE. IF BOND LOG SHOWS CMT TO SURFACE RUN TBG TO 1300' & CIRCULATE CMT TO SURFACE & CHECK BACKSIDE. CUT OFF CASING & RESTORE LOCATION. IF WELL WILL NOT PRESSURE TEST RUN TBG TO 2100' & PUMP 30 SX CMT WITH HULLS.

Plugging Proposal Received By: SCOTT ALBERG

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 07/23/2018 6:00 PM

KCC Agent: KEN SCOFIELD

Actual Plugging Report:

Perfs:

WELL NEVER COMPLETED 7/20/18: RIG UP & TAG BOTTOM AT 2324'. WELD HOLE IN 4 1/2" CASING AT SURFACE. PRESSURE TEST CASING. WOULD NOT HOLD. GAS POP NOTED WHILE WELDING CASING. RIG UP LOGGERS AND RUN BOND LOG. TOC @ 530'. PERFORATE 4 1/2" CASING AT 530'. LOAD HOLE & SHUT IN WELL FOR THE NIGHT. 7/23/18: RIH WITH TBG TO 2100'. PUMP 30 SX CMT WITH 100# HULLS. CIRCULATION ESTABLISHED ON BACKSIDE WHILE PUMPING THIS PLUG. PULL TBG TO 1300' & PUMP 20 SX CMT. PULL TBG TO 600' & PUMP 70 SX CMT TO SURFACE. PULL TBG OUT OF HOLE. TIE ON TO 4 1/2" CASING & PUMP 55 SX CMT TO CIRCULATE CMT UP BACKSIDE TO SURFACE. CMT HOLDING STEADY AT SURFACE BOTH INSIDE & OUT OF 4 1/2" CASING.

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE. CONTROL # 20180029

Plugged through: TBG

District: 01

Signed

RECEIVED

KANSAS CORPORATION COMMISSION

(TECHNICIAN)

RECEIVED
AUG - 1 2018
KCC DODGE CITY

AUG 15 2018

CONSERVATION DIVISION
WICHITA, KS

Form CP-2/3