

TO:

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-073-30068-00-00

Spot: SENWSESE

Sec/Twnshp/Rge: 11-24S-9E

800 feet from S Section Line,

800 feet from E Section Line

Lease Name: OLSON-ANDERSON

Well #: 26

County: GREENWOOD

Total Vertical Depth: 2250 feet

Operator License No.: 3599

Op Name: JB NORDMEYER, LLC DBA OLSON-AN

Address: 2253 P RD

EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2250		100 SX
SURF	8	60		25 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/13/2018 8:00 AM

Plug Co. License No.: 7719

Plug Co. Name: CHEEVER WELL SERVICE, INC.

Proposal Rcvd. from: BARNEY NORDMEYER

Company:

Phone: (620) 583-4711

Proposed Plugging Method: Pump 50' plug above Bartlesville formation. Pump 50' plug above Douglas formation. Pump cement from 200' to surface with perforations above Douglas and at 200'.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/13/2018 1:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Perfs:

Ran tubing to 2110' pumped 20 sxs cement, pulled tubing to 913' pumped 20 sxs cement, pulled tubing to 220' pumped 20 sxs cement to surface. gawl spacers between cement plugs, casing shot @ 913' & 220'.

Top	Bot	Thru	Comments
2172	2220		

RECEIVED  
KCC DIST # 3  
AUG 20 2018  
CHANUTE, KS

INVOICED  
AUG 20 2018


MH

Remarks:

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

810 E 7<sup>th</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



15-073-30018 0000  
**Cement or Acid Field Report**  
 Ticket No. **4078**  
 Foreman KEVIN MCGOY  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
8-13-18	1087	Olsen-Anderson #26	11	24	9	GW	Ks	
Customer <u>JB Nordmeyer OIL</u>			Unit #		Driver		Unit #	Driver
Mailing Address <u>2253 P Road</u>			105		DAVE G.			
			110		JASON H.			
			141		Zevi A.			
City <u>EUREKA</u>		State <u>Ks</u>	Zip Code <u>67045</u>					

Job Type P.T.A. Hole Depth \_\_\_\_\_ Slurry Vol. \_\_\_\_\_ Tubing 2 3/8  
 Casing Depth \_\_\_\_\_ Hole Size \_\_\_\_\_ Slurry Wt. \_\_\_\_\_ Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: SAFETY Meeting: Rig up to 2 3/8 Tubing. Spot Cement plugs as following inside 4 1/2 casing.

20 SKS @ 2110'  
Gel Spacer  
20 SKS @ 913'  
Gel Spacer  
20 SKS FROM 220' to SURFACE

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	785.00	785.00
C 107	15	Mileage	4.20	63.00
C 203	60 SKS	60/40 Pozmix Cement	13.40	804.00
C 206	200 #	Gel 4%	.21	42.00
C 108	2.58 TONS	Ton Mileage	M/C	365.00
C 113	2 HRS	80 BBL VAC TRUCK	90.00	180.00
C 224	3300 GALS	City water	10.00/1000	33.00
C 206	400 #	Gel Spacer	.21	84.00
<b>INVOICED</b>				
<b>AUG 20 2018</b>				
<u>THANK You</u>				
			Sub Total	2356.00
			Less 5%	117.80
			Sales Tax	176.70
			7.5%	
Authorization _____ Title _____			Total	2406.00

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.