

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-17704-00-00
Spot: NWNESEW Sec/Twnshp/Rge: 30-27S-10W
2349 feet from S Section Line, 3158 feet from E Section Line
Lease Name: CUNNINGHAM UNIT B Well #: 28
County: KINGMAN Total Vertical Depth: 3447 feet

Operator License No.: 3880
Op Name: KC RESOURCES, INC.

Address: P. O. BOX 6749
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	3403		500 SX
SURF	12.5	334		300 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/14/2017 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: JIM KRAFT Company: _____ Phone: (785) 252-7030

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 12/14/2017 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

11/21/2017 CIBP SET @ 3330' W/2 SX CEMENT ON TOP. CASING WAS PERFORATED @ 1450' & 900' & 390'. 12/11/17 RIG TTIH TO 1450' DISPLACE HOLE WITH 15 SX GEL, THEN SPOTTED 50 SX CLASS A CEMENT 3% CC. 12/12/17 TAGGED TOC @ 1295'. TTIH TO 900' SPOTTED 50 SX CEMENT, TTOH TO 390' CIRCULATED TO SURFACE W/250 SX CEMENT, TTOH, OPEN SURFACE CASING VALVES, SWEDGED UP 7" PUMPED ANOTHER 225 SX CEMENT TO BRING AROUND INTO 12.5" CASING. 12/14/17 DUG UP AND CUT CASING OFF, CEMENT AT SURFACE INSIDE 12.5", DOWN 40' INSIDE 7", TOPPED OFF W/ 15 SX CEMENT.

INVOICED

AUG 2'0 2018

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT. LICENSE IS SUSPENDED.

Plugged through: TBG

District: 02

Signed

B. J. Hope

(TECHNICIAN)