

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-01617-00-00
Spot: NWSWSE Sec/Twnshp/Rge: 19-27S-10W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: MILES B Well #: 7
County: KINGMAN Total Vertical Depth: 3997 feet

Operator License No.: 3880
Op Name: KC RESOURCES, INC.
Address: P. O. BOX 6749
SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3979		300 SX
SURF	10.75	381		200 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/31/2018 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Revd. from: JIM KRAFT Company: _____ Phone: (785) 252-7030

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 06/11/2018 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

Perfs:

5/31/18 SET CIBP AT 3300', BAILED 5 SX CEMENT ON PLUG. 6/4/18 HAD WELDER SPLIT CASING HEAD APART, SHOT CASING AT 1530' AND 1500', RAN TUBING INTO 1500' PUMPED 100# HULLS. 3% CC CLASS A CEMENT, PULLED TUBING OUT, TAGGED PLUG @ 1326'. 6/5/18 SHOT CAISNG AT 860', RAN TUBING PUMPED 35 SX CEMENT AND 100 LBS HULLS, PULLED TUBING OUT, SHOT CASING AT 463', SHOT 418'. 6/6/18 RAN BOND LOG - CEMENT ON BACKSIDE HAD BEEN SQUEEZED FROM TOP OF THE SALT TO 190'. RAN 180' OF 1". PUMPED 70 SX CEMENT, CIRCULATED OUT 8 5/8", RAN 2 3/8" TUBING TO 430', PUMPED 90 SX, CIRCULATED OUT 5.5" CASING. 6/11/18 TOPPED WELL OFF WITH 15 SX CEMENT.

INVOICED

AUG 20 2018

Remarks: DENIED TA - QUALITY WELL SERVICE PROVIDED CEMENT AND LOGGING TOOLS FOR THIS JOB.

Plugged through: CSG

District: 02

Signed B. J. Hope

(TECHNICIAN)