

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-29598-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 29-18S-10W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: MANKE Well #: 1
County: RICE Total Vertical Depth: 3305 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>3309</u>	PROD	4.375	3305		150 SX
Op Name: <u>EAGLE PETROLEUM, INC.</u>	SURF	8.625	245		160 SX
Address: <u>PO BOX 335</u> <u>ELLINWOOD, KS 67526</u>					

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/27/2018 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Revd. from: RON HICKEL Company: EAGLE PETROLEUM Phone: (620) 793-2037

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL Witness Type: PARTIAL
Date/Time Plugging Completed: 07/30/2018 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL RODS & TUBING. PERFORATE AT 1250', AND 300'. RUN TUBING TO 3200' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING UP TO 1250' AND WAIT 1.5 HOURS. RUN SWAB BAR DOWN AND TAGGED CEMENT AT 3250'. RUN TUBING BACK DOWN TO 3200' AND PUMPED 35 MORE SX'S COMMON WITH 3% CC AND 100#'S COTTON HULLS. PULL TUBING TO 1250' AND WAIT 1.5 HOURS. RUN DOWN WITH SWAB BAR- GOT TO 800'. DECISION MADE TO CLEAR TUBING-DETERMINED HOLE SOMEWHERE IN TUBING. PULL TUBING CLEAR OUT AND RUN DOWN WITH SWAB BAR TAGGING CEMENT AT 3200'. WILL COME BACK ON 7-30-18 WITH GOOD TUBING. ON 7-30-18, ATTEMPTED TO RUN TUBING TO 3200' AND ENCOUNTERED PLUG AT 1350'. PULLED TUBING TO 1250' AND PUMPED 35 SX'S COMMON WITH 3% CC. PULLED TUBING UP TO 750' AND WAITED 1 HOUR, TAGGED CEMENT AT 1250'. RUN TUBING BACK DOWN TO 1250' AND PUMPED 50 SX'S COMMON WITH 35 CC GETTING CEMENT CIRCULATION TO SURFACE. PULLED TUBING TO 300' AND CIRCULATED CEMENT TO SURFACE FROM BOTH CASINGS. PULLED TUBING OUT AND TOPPED OFF. USED APPROX. 270 SX'S.

Perfs:

Top	Bot	Thru	Comments
3205	3210	CSG	

INVOICED
AUG 20 2018

Remarks: GRESSEL PERF TICKET #2009, COPELAND CEMENT #C-45407.

Plugged through: TBG

District: 02

Signed Virgil Clothier
(TECHNICIAN)