

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-115-20790-00-00
Spot: W2E2NENW Sec/Twshp/Rge: 25-18S-4E
660 feet from N Section Line, 3040 feet from E Section Line
Lease Name: MEYER B Well #: 2
County: MARION Total Vertical Depth: 1300 feet

Operator License No.: 5192
Op Name: SHAWMAR OIL & GAS CO., INC.
Address: 1116 E MAIN PO BOX 9
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1450		
PROD	4.5	2335		75 SX
SURF	8.625	200		100 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/24/2018 12:00 AM
Plug Co. License No.: 5192 Plug Co. Name: SHAWMAR OIL & GAS CO., INC.
Proposal Rcvd. from: BENNY KEY Company: _____ Phone: (620) 381-1023

Proposed Plugging Method: AS PER KCC RULES & REGS. USUALLY THIS CONSISTS OF A 50' SAND PLUG AT BOTTOM COVERED WITH A 5 SACK CEMENT PLUG. FILL FROM 250' TO SURFACE WITH CEMENT (ANNULUS AND CASING). CUT CASING OFF BELOW GROUND LEVEL. RESTORE GROUND AS NEEDED.

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 07/31/2018 12:00 AM KCC Agent: JERRY SPARLING

Actual Plugging Report:

7-24-2018, RAN SAND LINE AND TAGGED BOTTOM @ 1248'. SANDED BACK TO 1085' TOPPED WITH 5 SX OF COMMON CEMENT WITH DUMP BAILER. 7-25-2018, RAN 1" DOWN BACKSIDE TO 250'. PUMPED 45 SX COMMON CEMENT AND CIRCULATED TO SURFACE. PULLED 1" AND RAN IN TO 250' AND PUMPED 25 SX AND CIRCULATED TO SURFACE. 7-31-18 TOPPED OFF CASING WITH 15 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
1085	1248	CSG	

INVOICED

AUG 2⁰ 2018

Remarks: 85 SX COMMON CEMENT TOTAL

Plugged through: CSG

District: 02

Signed


(TECHNICIAN)