

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-02674-00-00
Spot: SENWSW Sec/Twshp/Rge: 25-20S-9W
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: TOBIAS LEASE Well #: 8
County: RICE Total Vertical Depth: 3360 feet

Operator License No.: 34318

Op Name: BEREXCO LLC

Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP	5.5	3315		
CIBP	5.5	3340		
PROD	5.5	3355		100 SX
SURF	8.625	203		190 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/08/2018 11:00 AM

Plug Co. License No.: 34318

Plug Co. Name: BEREXCO LLC

Proposal Rcvd. from: DENNIS KIRMER

Company: BEREXCO LLC

Phone: (316) 772-6449

Proposed Plugging Method: AS PER KCC RULES & REGS. CONDITION OF WELL - POOR. CASING SQUEEZED AT 2241' - 2281 WITH 135 SX'S. CASING SQUEEZES AT 3268' AND 3280'.

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 08/08/2018 4:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU. CK BOTTOM. PERFORATE AT 1150', 750', AND 255'. RUN TUBING TO 3250' AND PUMP 50 SX'S COMMON CEMENT WITH 3% CC AND 100#'S COTTON HULLS. PULL TUBING UP TO 2850' AND PUMP 100 SX'S 60-40 POZ 4% GEL AND 200 #'S COTTON HULLS. PULL TUBING TO 1150' AND PUMP 35 SX'S COMMON CEMENT WITH 3% CC. PULL TUBING OUT AND WAIT 1.5 HOURS. RUN TUBING BACK IN AND TAGGED CEMENT AT 850'. PUMPED 50 SX'S 60-40 POZ AT 850', PULLED TUBING TO 400' AND CIRCULATED CEMENT TO SURFACE FROM BOTH CASINGS. PULLED TUBING OUT AND TOPPED OFF.

Top	Bot	Thru	Comments
3355	3360		OIL
3320	3322		CSG
3300	3305		CSG
3276	3278		CSG
3224	3256		CSG

INVOICED

AUG 20 2018

Remarks: DENIED TA WELL DUE TO HFLD. PERF TECH #14191. QUALITY OIL WELL CEMENT #920.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

1/2