

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-127-20037-00-00  
Spot: NESESESE Sec/Twnshp/Rge: 13-16S-7E  
338 feet from S Section Line, 227 feet from E Section Line  
Lease Name: DOWNES Well #: 1  
County: MORRIS Total Vertical Depth: 2729 feet

Operator License No.: 31142  
Op Name: PETROLEUM PROPERTY SERVICES, IN  
Address: 125 N MARKET SUITE 1251  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2721		50 SX
SURF	8.625	150		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/06/2018 3:30 PM  
Plug Co. License No.: 35499 Plug Co. Name: S & P WELL SERVICE, INC.  
Proposal Revd. from: CHUCK TONER Company: \_\_\_\_\_ Phone: (620) 546-4752

Proposed Plugging Method: AS PER THE KCC INSTRUCTIONS

Plugging Proposal Received By: JERRY SPARLING WitnessType: PARTIAL  
Date/Time Plugging Completed: 08/06/2018 3:30 PM KCC Agent: JERRY SPARLING

Actual Plugging Report:

RETRIEVABLE CIBP @ 2605'. SQUEEZE JOB FROM 506' TO 202' DRILLED 150' PAST 506'. COULD NOT GET INTEGRITY 650 SX CEMENT. BULLHEAD SQUEEZE TO 1600 PSI. COULD NOT MAINTAIN PRESSURE. THEN DECIDED TO PLUG THIS WELL. 8-6-2018. PERF-TECH WIRELINE SERVICES BOND LOG TRUCK ARRIVED AND LOGGED WELL FROM 655; TO SURFACE PERFORATED @ 250'. GLOBAL HOOKED UP TO TUBING AND PUMPED 12 SX AND CIRCULATED TO SURFACE. WAITED 2 HOURS FOR CEMENT TO SET UP. HOOKED UP TO BACKSIDE AND PUMPED 10 SX AND CIRCULATED TO SURFACE. PUMPED 5 SX TO TOP OFF CASING.

Perfs:

INVOICED  
AUG 20 2018

Remarks: GLOBAL 27 SX TOTAL. CHECKED TOP PLUG 8-7-18 STANDING FULL.

Plugged through: CSG

District: 02

Signed Jerry Sparring  
(TECHNICIAN)