

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-125-29848-00-01

Spot: NESWSWNW

Sec/Twnshp/Rge: 14-32S-15E

3088 feet from S Section Line,

4642 feet from E Section Line

Lease Name: SNYDER

Well #: 5

County: MONTGOMERY

Total Vertical Depth: 1236 feet

Operator License No.: 35497

Op Name: REDBUD OIL & GAS OPERATING, LLC

Address: 16000 STUEBNER AIRLINE RD SUITE 3
SPRING, TX 77379

String	Size	Depth (ft)	Pulled (ft)	Comments
--------	------	------------	-------------	----------

PROD	4.5	1225		130 SX
------	-----	------	--	--------

SURF	8.625	20		5 SX
------	-------	----	--	------

Well Type: SWD

UIC Docket No: D27666.0

Date/Time to Plug:

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: AARON HAMMERSCHMID Company:

Phone: (620) 331-7870

Proposed Plug in accordance with KCC rules
Plugging Method:

Plugging Proposal Received By: DUANE SIMS

WitnessType: NONE

Date/Time Plugging Completed: 07/26/2018 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1200' gelled hole and spotted 5 sack plug. Pulled up to 700' and spotted 5 sack plug. Pulled up to 225' and circulated cement to surface. Pulled 1" and topped well off. A total of 35 sacks of cement with 3% gell was used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1214	1224		

RECEIVED
KCC DIST # 3
AUG 21 2018
CHANUTE, KS

INVOICED


AUG 21 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)