

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26681-00-01
Spot: NESWNE Sec/Twnshp/Rge: 32-33S-13E
3406 feet from S Section Line, 1506 feet from E Section Line
Lease Name: GOFF Well #: 11
County: CHAUTAUQUA Total Vertical Depth: 1708 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1700		310 SX
SURF	8.625	42		30 SX
TI	2.375	1293		

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: BUDDY FINNEY Company: _____ Phone: (620) 374-2133

Proposed Plugging Method: RUN 1" IN TO TD PUMP GEL & THEN PUMP A 50' CEMENT PLUG; PULL PIPE UP TO 665' PUMP 50' CEMENT PLUG; PULL PIPE TO 330' PUMP CEMENT TO SURFACE; PULL REST OF PIPE & TOP OFF WITH CEMENT

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 07/23/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1330' gelled hole and spotted 5 sack plug. Pulled up to 750' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 65 sacks of cement with 3% gell was used to plug this well.

Perfs:

Top	Bot	Thru'	Comments
1360			
1286	1290		

RECEIVED
KCC DIST # 3
AUG 21 2018
CHANUTE, KS

DS

INVOICED
AUG 21 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC

Plugged through: TBG

District: 03

Signed 
(TECHNICIAN)