

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-21635-00-00
Spot: SESWSW Sec/Twnshp/Rge: 21-33S-13E
180 feet from S Section Line, 4333 feet from E Section Line
Lease Name: BALLARD Well #: 9-E
County: CHAUTAUQUA Total Vertical Depth: 1050 feet

Operator License No.: 4448
Op Name: PERKINS OIL ENTERPRISES, INC.
Address: PO BOX 707
HOWARD, KS 67349

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1050		75 SX
SURF	7	50		45 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Revd. from: BUDDY FINNEY Company: _____ Phone: (620) 374-2133

Proposed Plugging Method: RUN 1" IN TO TD PUMP GEL & THEN PUMP A 50' CEMENT PLUG; PULL PIPE UP TO 500' PUMP 50' CEMENT PLUG; PULL PIPE TO 275' PUMP CEMENT TO SURFACE; PULL REST OF PIPE & TOP OFF WITH CEMENT

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 07/24/2018 10:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 860' gelled hole and spotted 5 sack plug. Pulled up to 550' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" and topped well off. A total of 35 sacks of cement with 3% gell was used to plug this well.

RECEIVED
KCC DIST # 3
AUG 21 2018
CHANUTE, KS

DS


INVOICED
AUG 21 2018

Remarks: WELL WAS PLUGGED DUE TO COMPLIANCE AGREEMENT SIGNED BY OPERATOR WITH THE KCC

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)