

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-22466-00-00  
Spot: SENENW Sec/Twship/Rge: 29-28S-13E  
4284 feet from S Section Line, 3281 feet from E Section Line  
Lease Name: FINK Well #: A-1  
County: ELK Total Vertical Depth: 1530 feet

Operator License No.: 33539  
Op Name: CHEROKEE WELLS LLC  
Address: P.O. BOX 296  
FREDONIA, KS 66736

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1520		165 SX
SURF	8.625	44		10 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2018 12:00 AM  
Plug Co. License No.: 99975 Plug Co. Name: COMPANY SERVICING TOOLS  
Proposal Revd. from: JEFF MORRIS Company: \_\_\_\_\_ Phone: (620) 378-3650

Proposed Plugging Method: Set 50' 50/50 Poz blend cement plug on TD to approx. 1480'. Fill with 9# (minimum) bentonite gel to approx. 765', then set 50' cement plug to 715'. Fill with gel to approx. 150', then cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 07/02/2018 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Well had never been perforated. Ran 1" spool hose to 1500' gelled hole and spotted 5 sack plug. Pulled up to 850' and spotted 5 sack plug. Pulled up to 275' and circulated cement to surface. Pulled 1" spool hose out of well and topped well off. A total of 32 sacks of cement with 4% gell was used to plug this well.

RECEIVED  
KCC DIST # 3  
AUG 21 2018  
CHANUTE, KS

DS

INVOICED


AUG 21 2018

Remarks: WELL PLUGGED DUE TO 10 YEAR TA RULE.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)