

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-049-21717-00-00  
Spot: NWNEENE Sec/Twnshp/Rge: 28-29S-9E  
4953 feet from S Section Line, 364 feet from E Section Line  
Lease Name: SMITH A Well #: 2  
County: ELK Total Vertical Depth: 2580 feet

Operator License No.: 32874  
Op Name: VEEM JADE OIL & GAS LLC  
Address: 11-117 S GRANITE AVE  
TULSA, OK 74137

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2470		150 SX
SURF	7	64		35 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/23/2018 12:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: KEVIN WARDLOW Company: \_\_\_\_\_ Phone: (620) 330-3666

Proposed Plugging Method: 20 sacs on bottom, 10 sacs per intermediate plugs with gel spacers and 500 foot to surface. Set Gel Spacers between cement plugs. Perforate 300 foot and intermediate wherever State recommends. 60/40 poz cement with 4% gel.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE  
Date/Time Plugging Completed: 07/23/2018 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Shot 4.5" casing off at 500' and pulled casing. Ran 2" to 2100' gelled hole and spotted 10 sack plug. Pulled up to 1850' and spotted 20 sack plug. Pulled up to 517" and circulated cement to surface. Pulled 2" and topped well off. A total of 197 sacks of 60/40 pozmix with 4% gell was used to plug this well.

RECEIVED  
KCC DIST # 3  
AUG 21 2018  
CHANUTE, KS

INVOICED  
AUG 21 2018

DS

Remarks: WELL WAS PLUGGED DUE TO DENIED CP-111 AND FAILED CIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)