

6-13

2-070561

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-159-21,112.0000

NW NW SW, SECTION 18 TOWNSHIP 20 RANGE 10W

OPERATOR LICENSE # 3208

FEET FROM S SECTION LINE

FEET FROM E SECTION LINE

OPERATOR K & N PETROLEUM INC
NAME & 513 WEST 6TH STREET
ADDRESS ELLINWOOD, KS 67526

LEASE NAME: BERSCHIEDT D-1

COUNTY: RICE

WELL TOTAL DEPTH: 3279' *106.57*

PIPE: 4-1/2" @ 3272'

SURFACE CASING: 8-5/8" @ 229'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: _____

ADDRESS: _____ LICENSE: _____

COMPANY TO PLUG AT: HOUR: 2:00 DAY: 13 MONTH: 6 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: MANNY

COMPANY NAME: _____ PHONE: 316-

WERE: SAND TO 2970' & 4 SX - 35 SX @ 1250' - 35 SX @ 900' - 270' TO 0'

PLUGGING PROPOSAL RECEIVED BY: J. LUTHI

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 5:00 DAY: 13 MONTH: 6 YEAR: 1995

ACTUAL PLUGGING REPORT:

SANDED BOTTOM TO 2970' & 4 SX OF COMMON - SHOT 4-1/2"
CSG OFF @ 2300' - PULLED TO 1256' - PUMPED 35 SX -
PULLED TO 900' - PUMPED 35 SX - PULLED TO 270' - CIRC
CMT TO SURF

RECEIVED

KANSAS CORPORATION COMMISSION

REMARKS: ALLIED #1007 60/40 4% JUN 29 1995

IF YOU OBSERVE THIS PLUGGING.
INVOICED

DATE 6-30-95

INV. NO. 43017

Jack Luthi
Jack Luthi (AGENT)

CONSERVATION DIVISION
WICHITA, KS

FORM CP-2/3
REV. 3/90