

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-159-21,772.0000

NE, Sec. 18, T 20 S, R 10 W/4

1220' feet from N/S section line

330' feet from W/S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6039

Lease Name Peters Well # 1

Operator: L.D. Drilling, Inc.
Name & Address Route 1, Box 183-B
Great Bend, Kansas 67530

County Rice

Well Total Depth 3314 feet 107.70

Conductor Pipe: Size feet

Surface Casing: Size 8 3/4 feet 288

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Operator and Halliburton Co. License Number 6039 Rig # 567

Address

Company to plug at: Hour: 8:00 A Day: 16 Month: January Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Don Papp

(company name) L.D. Drilling, Inc. (phone) 913 653 7625

were: Fill hole with heavy mud. Pump 30 sacks 50/50 Pozmix w/4% gel through drill pipe at 3290'. Pump 50 sacks cement through drill pipe at 350'. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Cement ratihole with 10 sacks cement

Signed [Signature]
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:30 PM Day: 16 Month: January Year: 1984

ACTUAL PLUGGING REPORT Hole Filled with heavy mud to cellar. 30 sacks 50/50 Pozmix pumped through drill pipe at 3290'. 50 sacks 50/50 Pozmix pumped through drill pipe at 350'. Hole Filled with mud to 40'. Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sack cement through 1 Joint drill pipe.


Remarks: Halliburton Ticket # 780502

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

FEB 02 1984

CONSERVATION DIVISION
Wichita, Kansas



INVOICE (TECHNICIAN) [Signature] 2-3-84

DATE 2-3-84
INV. NO. 0043

FORM CP-2/3
Rev. 9-82

M. U.

RPW ✓